



VEHICLES / PLANT / DELIVERIES - EXCLUSION ZONE

CAUTION

Use where work vehicles, deliveries, EWP or mobile plant interact with residents or pedestrians.

PEDESTRIANS MUST STAY OUT OF THE OPERATING ZONE

PEDESTRIANS / RESIDENTS

- Use the designated pedestrian route and follow directions from the spotter/site team.
- Do not walk behind reversing vehicles or enter between plant and fixed objects.
- Keep children and pets clear of driveways, delivery areas and mobile plant.
- Do not cross barriers or move cones/signage.
- If safe access to the home is affected, contact the SCS site lead before proceeding.

DRIVERS / OPERATORS

- Separate vehicles and pedestrians wherever practicable using barriers and controlled routes.
- Use a spotter where visibility is restricted or people may enter the operating area.
- Reverse only when the route is clear and controls are in place.
- Keep speeds low and appropriate to the site. Follow any posted project limit.
- Schedule deliveries to reduce conflict with residents, schools, public access and other trades.
- Stop movement immediately if a person enters the exclusion zone.